

Construction Bulk Commodity Summary

The construction of the NF Facility will include the following major commodities, approximately:

347,000 cubic yards total

122,000	cubic yards of structural concrete
127,000	cubic yards CLSM fill material for soils stabilization
98,000	cubic yards of high-pressure injected grout for soils stabilization
123,000	linear feet of piping > 1/2"
95,000	linear feet of process and instrument tubing < 1/2"
1,040,000	linear feet of conduit and raceway
2,610,000	linear feet of wire, cable and fiber
1,580,000	pounds of ductwork
975,000	pounds of duct support steel